ABBREVIATIONS

@	AT
A/C	AIR-CONDITIONING
AB	ANCHOR BOLT
ABC	AGGREGATE BASE COURSE
ACS	ACCESS PANEL
ACT	ACOUSTICAL CEILING TILE
ADJ	ADJACENT
AFF	ABOVE FINISHED FLOOR
ALT	ALTERNATE
ALUM	ALUMINUM
ANOD	ANODIZED CLEAR
AUTO	AUTOMATIC
BD	BOARD, BEAD
BFF	BELOW FINISHED FLOOR
BLDG	BUILDING
BLK(IG)	BLOCK(ING)
BM	BEAM
BOT	BOTTOM
BRG	BEARING
BSMT	BASEMENT
BU	BUILT-UP
C	CHANNEL
C TO C	CENTER TO CENTER
CA	CARD ACCESS
CAB	CABINET
CB	CATCH BASIN
CEM	CEMENT
CEM PLAS	CEMENT PLASTER
CER	CERAMIC
CFCI	CONTRACTOR FURNISH/CONTRACTOR INSTAL
CFM	CUBIC FEET PER MINUTE
CG	CORNER GUARD
CI	CAST IRON
CIP	CAST IRON PIPE, CAST-IN-PLACE
CJ	CONTROL JOINT
CKT	CIRCUIT
CL	CENTER LINE
CLNG	CEILING
CLR	CLEAR
CMP	CORRUGATED METAL PIPE
CMU	CONCRETE MASONRY UNIT
CO	CLEAN-OUT
COL	COLUMN
COMB	COMBINATION
CONC	CONCRETE
CONN	CONNECT
CONSTR	CONTRUCTION
CONT	CONTINUE
CORR	CORRIDOR
CPT	CARPET
CSK	COUNTER SUNK
CT	CERAMIC TILE
CU	CUBIC
CU FT	CUBIC FEET
CW	COLD WATER PIPING
D	DEEP, DEPTH
DBL	DOUBLE
DEMO	DEMOLISH
DEPT	DEPARTMENT
DET	DETAIL
DF	DRINKING FOUNTAIN
DIA	DIAMETER
DIAG	DIAGONAL
DIM	DIMENSION
DISP	DISPENSER
DMPF	DAMPPROOFING
DR	DOOR
DS	DOWNSPOUT
DWG	DRAWING
E	EAST
EA	EACH
EF	EACH FACE
EIFS	EXT. INSULATION AND FINISH SYSTEM
EJ	EXPANSION JOINT
EL	ELEVATION
ELEC	ELECTRIC(AL)
ELEV	ELEVATOR
EMER	EMERGENCY
EOS	EDGE OF SLAB
EQ	EQUAL
EQUIP	EQUIPMENT
EST	ESTIMATE
ETC	ETCETERA
EW	EACH WAY
EWC	ELECTRIC WATER COOLER
EXC	EXCAVATE(ION)
EXH	EXHAUST
EXIST	EXISTING
EXP	EXPANSION
EXP BT	EXPANSION BOLT
EXT	EXTERIOR
FA	FIRE ALARM
FACP	FIRE ALARM CONTROL PANEL
FCO	FLOOR CLEAN-OUT
FD	FLOOR DRAIN
FDTN	FOUNDATION
FE	FIRE EXTINGUISHER
FEC	FIRE EXTINGUISHER CABINET
FF EL	FINISHED FLOOR ELEVATION
FHC	FIREHOSE CABINET
FHR	FIREHOSE RACK
FIN	FINISH(ED)
FLASH	FLASHING
FLEX	FLEXIBLE
FLR	FLOOR
FLUOR	FLUORESCENT
FM	FACTORY MUTUAL
FOW	FACE OF WALL
FP	FIREPROOF
FR	FIRE RETARDANT
FRP	FIBERGLASS REINFORCED PANEL
FT	FOOT, FEET
FURG	FURRING
FUT	FUTURE
G	GROUND
GA	GAGE
GALV	GALVANIZED
GC	GENERAL CONTRACTOR
GFCR	GLASS FIBER REINFORCED CONCRETE
GI	GALVANIZED IRON
GL	GLASS, GLAZING
GPM	GALLONS PER MINUTE
GYP	GYPSUM
GYP BD	GYPSUM BOARD
H	HIGH
HB	HOSE BIBB
HC	HOLLOW CORE, HANDICAP
HD	HEAVY DUTY
HDBD	HARDBOARD
HDWD	HARDWOOD
HDWR	HARDWARE
HM	HOLLOW METAL
HORIZ	HORIZONTAL
HP	HORSE POWER
HT	HEIGHT
HVAC	HEATING/VENTILATING/AIR-CONDITIONING
HW	HOT WATER
ID	INSIDE DIAMETER
IF	INSIDE FACE
INCL	INCLUDED
INFO	INFORMATION
INSUL	INSULATION
INT	INTERIOR
INV	INVERT
INV EL	INVERT ELEVATION
J-BOX	JUNCTION BOX
JAN CLO	JANITOR CLOSET
KD	KNOCKED DOWN
KIT	KITCHEN
KO	KNOCKOUT
KPL	KICK PLATE
L	ANGLE
LAB	LABORATORY
LAM	LAMINATE
LAV	LAVATORY
LB	POUND
LF	LINEAR FOOT
LG	LONG, LENGTH
LH	LEFT HAND
LL	LIVE LOAD
LLH	LONG LEG HORIZONTAL
LLV	LONG LEG VERTICAL
LPT	LOW POINT
LT	LIGHT
LT WT	LIGHTWEIGHT
LVR	LOUVER
MATL	MATERIAL
MAU	MAKE-UP AIR UNIT
MAX	MAXIMUM
MB	MACHINE BOLT
MECH	MECHANICAL
MED	MEDIUM, MEDICAL
MEMB	MEMBRANE
MEZZ	MEZZANINE
MFR	MANUFACTURER
MH	MANHOLE
MIN	MINIMUM
MISC	MISCELLANEOUS
MM	MILLIMETER
MO	MASONRY OPENING
MOD	MODIFY
MR	MOISTURE-RESISTANT
MTD	MOUNTED
MTL	METAL
MVBL	MOVABLE
N	NORTH
NA	NOT APPLICABLE
NEUT	NEUTRAL
NFPA	NATIONAL FIRE PROTECTION ASSOC.
NIC	NOT IN CONTRACT
NO	NUMBER
NOM	NOMINAL
NRC	NOISE REDUCTION COEFFICIENT
NTS	NOT TO SCALE
OA	OVERALL
OC	ON CENTER
OD	OUTSIDE DIAMETER
OF	OUTSIDE FACE
OF/CI	OWNER FURNISH/CONTRACTOR INSTALL
OF/OI	OWNER FURNISH/OWNER INSTALL
OFC	OFFICE
OH	OVERHANG
OPH	OPPOSITE HAND
OPNG	OPENING
OPP	OPPOSITE
ORD	OVERFLOW ROOF DRAIN
PAR	PARALLEL
PBD	PARTICLEBOARD
PC	PIECE
PCC	PRECAST CONCRETE
PCF	POUNDS PER CUBIC FOOT
PERF	PERFORATE(D)
PERIM	PERIMETER
PERP	PERPENDICULAR
PL	PROPERTY LINE
PLAM	PLASTIC LAMINATE
PLAS	PLASTER
PLBG	PLUMBING
PLF	POUNDS PER LINEAR FOOT
PLYWD	PLYWOOD
PNL	PANEL
PR	PAIR
PREFAB	PREFABRICATED
PREFIN	PREFINISHED
PSF	POUNDS PER SQUARE FOOT
PSI	POUNDS PER SQUARE INCH
PT	PAINT
PT	PRESSURE TREATED
PTD	PAPER TOWEL DISPENSER
PTN	PARTITION
PTR	PAPER TOWEL RECEPTACLE
PUR	PURLIN
PVC	POLYVINYL CHLORIDE
QT	QUARRY TILE
QTR	QUARTER
QTY	QUANTITY
R	RADIUS, RISER, ROUND
RA	RETURN AIR
RB	RESILIENT BASE
RCP	REFLECTED CEILING PLAN
RD	ROOF DRAIN
REC	RECESSED
REF	REFERENCE
REINF	REINFORCE(D,ING)
REQD	REQUIRED
RESIL	RESILIENT
REV	REVISION, REVERSE
RH	RIGHT HAND
RM	ROOM
RO	ROUGH OPENING
ROW	RIGHT-OF-WAY
RWL	RAINWATER LEADER
S	SOUTH
SA	SUPPLY AIR
SAP	SUSPENDED ACOUSTICAL PANEL
SCHED	SCHEDULE
SCW	SOLID CORE WOOD
SD	STORM DRAIN
SDG	SIDING
SECT	SECTION
SF	SQUARE FEET
SHR	SHOWER
SHT	SHEET
SHTHG	SHEATHING
SIM	SIMILAR
SM	SHEET METAL
SPCL	SPECIAL
SPEC	SPECIFICATION
SPKR	SPEAKER
SQ	SQUARE
SS	SERVICE SINK, STANDING SEAM
SST	STAINLESS STEEL
ST	STREET
STD	STANDARD
STOR	STORAGE
STRUCT	STRUCTURAL
SUSP	SUSPENDED
SV	SHEET VINYL
SW	SWITCH
SWR	SEWER
SYMM	SYMMETRICAL
SYS	SYSTEM
T	TREAD
T&G	TONGUE AND GROOVE
TD	TRENCH DRAIN
TEL	TELEPHONE
TERR	TERRAZZO
THK	THICK(NESS)
TK BD	TACKBOARD
TMPD	TEMPERED
TO	TOP OF
TOB	TOP OF BEAM
TOC	TOP OF CURB/TOP OF CONCRETE
TOC	TOP OF CURB
TOD	TOP OF DECK
TOF	TOP OF FOOTING
TOM	TOP OF MASONRY
TOP	TOP OF PARAPET/TOP OF PAVEMENT
TOS	TOP OF STEEL
TOW	TOP OF WALL
TPD	TOILET PAPER DISPENSER
TTB	TELEPHONE TERMINAL BOARD
TV	TELEVISION
TYP	TYPICAL
UBC	UNIFORM BUILDING CODE
UGND	UNDERGROUND
UL	UNDERWRITERS' LABROATORY
UNFIN	UNFINISHED
UNO	UNLESS NOTED OTHERWISE
UR	URINAL
V	VENT
VB	VAPOR BARRIER
VCP	VITRIFIED CLAY PIPE
VCT	VINYL COMPOSITION TILE
VERT	VERTICAL
VEST	VESTIBULE
VIF	VERIFY IN FIELD
VTR	VENT THROUGH ROOF
VWC	VINYL WALL COVERING
W	WEST, WIDE(TH), WASTE
W/	WITH
W/O	WITHOUT
W/W	WALL TO WALL
WC	WATERCLOSET
WD	WOOD
WDW	WINDOW
WGL	WIRE GLASS
WH	WALL HUNG, WATER HEATER
WI	WROUGHT IRON
WP	WATERPROOF
WR	WATER RESISTANT
WS	WEATHERSTRIP
WSCT	WAINSCOT
WT	WEIGHT
WW	WASTEWATER
YD	YARD

ROOF PLAN LEGEND

- EXHAUST FAN
- ROOF DRAIN
- ROOF VENT
- ROOF HATCH
- ROOFTOP MECHANICAL EQUIPMENT
- ROOFTOP MECHANICAL EQUIPMENT
- THROUGH-WALL SCUPPER
- SKYLIGHT
- E.J. — EXPANSION JOINT COVER ASSEMBLY

FLOOR PLAN LEGEND

WALL TYPES:

- DEMOLITION
- NEW CONSTRUCTION

FIRE RATING WALL TYPES:

- 30 MIN FIRE BARRIER
- 1 HR FIRE BARRIER
- 2 HR FIRE BARRIER
- TRAVEL DISTANCE

OTHER WALL-MOUNTED COMPONENTS:

- CORNER GUARDS
- FEC — FULL RECESSED FIRE EXTINGUISHER CABINET
- FEC — SEMI-RECESSED FIRE EXTINGUISHER CABINET
- FE — SURFACE MOUNTED FIRE EXTINGUISHER BRACKET
- DENOTES OVERHEAD FIRE SHUTTER
- EXPANSION JOINT

FLOOR-MOUNTED COMPONENTS:

- FLOOR DRAIN
- FLOOR SINK
- EW — EYE/FACE WASH AND SHOWER STATION

CEILING PLAN LEGEND

- START POINT
- F — FIRE ALARM PULL STATION
- F — FIRE ALARM AUDIO/VISUAL DEVICE
- I — HEAT/THERMAL DETECTOR
- OS — OCCUPANCY SENSOR
- CEILING FAN
- VOICE ENHANCEMENT SPEAKER (CONTRACTOR FURNISHED, CONTRACTOR INSTALLED
- INTERCOM (CONTRACTOR FURNISHED, CONTRACTOR INSTALLED
- MS — MOTION SENSOR
- EXIT SIGN
- E — EMERGENCY LIGHT
- ACCESS PANEL (ACS)
- EXTERIOR LIGHT FIXTURE
- CEILING MOUNTED WALL PROJECTOR
- TRACK LIGHTING
- SUSPENDED UPLIGHT
- SUSPENDED UPLIGHT
- STRIP LIGHTING FIXTURE LENGTH VARIES
- COVE LIGHT
- 30" DEEP RADIANT
- PHOTO CELL
- SMOKE DETECTOR
- INTERCOM SPEAKER
- CLASSROOM SPEAKER
- AUDIO/VISUAL FIXTURE
- CAMERA
- TONE/VISUAL FIXTURE
- CT — CCTV SURVEILLANCE FIXTURE
- SUSPENDED ACOUSTICAL CEILING: 1'X1', 2'X2', & 2'X4' SYSTEMS
- GYPSUM WALLBOARD, CEMENT OR GYP PLASTER
- EXPOSED STRUCTURE
- EXISTING TO REMAIN
- WOOD T&G CEILING
- SUPPLY DIFFUSER
- SUPPLY DIFFUSER
- RETURN AIR GRILLE
- RETURN REGISTER
- EXHAUST GRILLE
- FORCE AIR DIFFUSER
- SIDE WALL DIFFUSER
- 2' X 4' LIGHT FIXTURE
- 2' X 2' LIGHT FIXTURE
- 1' X 2' LIGHT FIXTURE
- 1' X 1' LIGHT FIXTURE
- LIGHT FIXTURE LENGTH VARIES
- WALL MOUNTED LIGHT FIXTURE
- WALL MOUNTED LIGHT FIXTURE
- RECESSED DOWNLIGHT

ANNOTATION LEGEND

- TITLE 12" = 1'-0" / A1 — VIEW TITLE
- A1 / A101 — BUILDING ELEVATION
- A1 / A101 — INTERIOR ELEVATION
- 1 / A101 — BUILDING SECTION
- 1 / A101 — WALL SECTION
- A1 / A101 — DETAIL
- ROOM NAME / 101 — ROOM NAME & NUMBER
- 101A — DOOR NUMBER
- HM-X — FRAME TYPE
- A L — WINDOW TYPE
- A — STOREFRONT TYPE
- A01 — WALL TYPE
- LEVEL 100'-0" — ELEVATION
- X'- XX" — CEILING HEIGHT (AFF)
- 1 / A — COLUMN GRID
- 1 — REVISION
- PT-X — WALL FINISH
- RB-X — BASE FINISH
- VCT-X — FLOOR FINISH
- PT-X — DESIGNATED WALL FINISH
- VCT-X — DESIGNATED FLOOR FINISH
- XXX / XXX — MILLWORK COUNTERTOP/SPLASH MILLWORK WALL OR BASE CABINETS
- ACCESSIBLE ROOMS WITH MOBILITY FEATURES
- ACCESSIBLE ROOMS WITH COMMUNICATION FEATURES
- NORTH ARROW

MATERIAL LEGEND

- EARTH
- GLASS
- AGGREGATE BASE COURSE
- SAND, MORTAR, GYP BD, GROUT, PLASTER
- CONCRETE
- CONCRETE MASONRY UNIT
- BRICK
- STEEL
- RIGID INSULATION/ SPRAY FOAM INSULATION
- BATT INSULATION
- ACOUSTICAL PANEL
- PLYWOOD, OSB
- FINISH WOOD
- DIMENSIONAL LUMBER, CONTINUOUS
- DIMENSIONAL LUMBER BLOCKING
- EXISTING

GENERAL ARCH. NOTES

1. EXTERIOR DIMENSIONS GIVEN TO THE EXTERIOR FACE OF FRAMING (STUDS). DIMENSIONS TO INTERIOR PARTITIONS ARE TO THE FACE OF STUD OR CMU UNLESS NOTED OTHERWISE.
2. LARGE SCALE DETAILS AND PLANS TAKE PRECEDENCE OVER SMALL SCALE DRAWINGS.
3. ALL ITEMS ARE CONSIDERED TO BE "NEW" UNLESS NOTED OTHERWISE.
4. COORDINATE AND VERIFY ALL DIMENSIONS, OPENINGS AND CONDITIONS WITH CIVIL, STRUCTURAL, MECHANICAL, ELECTRICAL AND ALL OTHER PERTINENT DRAWINGS AND TRADES PRIOR TO CONSTRUCTION. NOTIFY ARCHITECT OF DISCREPANCIES AS SOON AS POSSIBLE.
5. DO NOT SCALE DRAWINGS.
6. ALL DETAILS ARE TYPICAL, INCORPORATE INTO PROJECT AT APPROPRIATE LOCATIONS WHETHER SPECIFICALLY INDICATED OR NOT.
7. HINGE SIDE OF ALL DOORS ARE LOCATED 4" FROM ADJACENT WALL UNLESS NOTED OTHERWISE.
8. NOT USED.
9. THE DRAWINGS & SPECIFICATIONS ARE COMPLIMENTARY DOCUMENTS NEITHER TAKE PRECEDENT OVER THE OTHER. CONFLICTS IN SPECIFICATIONS AND DRAWINGS SHALL BE BROUGHT TO THE ATTENTION OF THE ARCHITECT FOR CLARIFICATION.
10. THIS SET OF DRAWINGS INDICATES GENERAL SCOPE OF THE PROJECT. THE DRAWINGS DO NOT NECESSARILY INDICATE OR DESCRIBE ALL WORK REQUIRED FOR FULL PERFORMANCE AND COMPLETION OF THE REQUIREMENTS OF THE CONTRACT. ON BASIS OF SCOPE INDICATED OR DESCRIBED, CONTRACTOR SHALL FURNISH ALL LABOR, MATERIAL AND EQUIPMENT REQUIRED FOR PROPER EXECUTION AND COMPLETION OF THE WORK.
11. ALL CONSTRUCTION SHALL COMPLY WITH THE REQUIREMENTS OF APPLICABLE LOCAL, STATE AND FEDERAL CODES OR REGULATIONS.
12. ALL NEW CONSTRUCTION SHALL MEET CURRENT REQUIREMENTS OF THE AMERICANS WITH DISABILITIES ACT.
13. THE CONTRACTOR SHALL VERIFY THE LOCATION OF EXISTING UNDERGROUND UTILITIES BEFORE PROCEEDING WITH EXCAVATION, TRENCHING OR SIMILAR WORK. THESE DRAWINGS DO NOT CERTIFY THE EXISTENCE OF UTILITIES WHICH MAY BE PRESENT BUT UNRECORDED OR UNDETECTED.
14. PROVIDE LINTELS OR HEADERS AS REQUIRED OR DIRECTED OVER OPENINGS PENETRATED BY MECHANICAL EQUIPMENT.
15. PROVIDE MIN. 2X6 FIRE RETARDANT WOOD OR STEEL PLATE BLOCKING BETWEEN STUDS AT MOUNTING LOCATIONS FOR TOILET ACCESSORIES, HANDRAILS, GUARDRAILS, MILLWORK AND OTHER WALL MOUNTEDITEMS.
16. PROVIDE CODE COMPLIANT NON-COMBUSTIBLE BLOCKING, SUPPORTS, ETC., FOR SECURE, INSTALLATION OF WALL MOUNTED ITEMS. CONTRACTOR TO DETERMINE TYPE OF BLOCKING AND ANCHORING AS REQUIRED TO SUIT INSTALLATION AND WALL CONDITION. REFER TO ARCHITECTURAL DRAWINGS FOR STANDARD DETAILS AND MOUNTING HEIGHTS.
17. PROVIDE SECURE AND PERMANENT ANCHORAGE FOR CEILING FURRING AND OTHER CEILING MOUNTED ITEMS. SIESMIC REQUIREMENTS APPLY.
18. PROVIDE FIRE STOPPING AT ALL PENETRATIONS OF WALLS AND FLOORS AS SPECIFIED IN SPEC SECTION - FIRESTOPPING.
19. NOT USED.
20. ALL SUBSTITUTIONS OF MATERIALS AND ASSEMBLIES MUST BE APPROVED BY ARCHITECT IN ACCORDANCE WITH DIVISION 1 SPECIAL CONDITIONS.
21. CONTRACTOR IS REQUIRED TO PROVIDE CONTROL AND EXPANSION JOINTS IN ALL ASSEMBLIES PER SPECIFICATION.
22. CONTRACTOR SHALL PROVIDE ACCESS TO ALL FIRE DAMPERS AND SPRINKLER HEADS.
23. ALL PIPING, DUCTWORK AND CONDUIT TO BE CONCEALED UNLESS NOTED OTHERWISE.
24. ALL EXISTING SITE COMPONENTS TO REMAIN SHALL BE PROTECTED DURING CONSTRUCTION. ALL DAMAGED SURFACES AND EQUIPMENT SHALL BE REPAIRED OR REPLACED BY CONTRACTOR AS REQUIRED BY THE OWNER'S REP.
25. SITE SURVEY IS PROVIDED BY OTHERS AND IS INCLUDED FOR INFORMATION ONLY. ALL CONDITIONS TO BE FIELD VERIFIED BY CONTRACTOR.
26. CONTRACTOR SHALL MAINTAIN SITE DRAINAGE DURING CONSTRUCTION.
27. CONTRACTOR SHALL MAINTAIN A CLEAN AND SECURE SITE AS REQUIRED BY DIVISION 1 - CONSTRUCTION FACILITIES AND TEMPORARY CONTROLS.
28. VERIFY THE FOLLOWING WITH THE RESPECTIVE TRADES:
    A. SIZES AND LOCATIONS FOR BACKING/BLOCKING REQUIRED FOR MOUNTING MECH. AND/OR ELEC. EQUIPMENT
    B. SIZES AND LOCATIONS OF MECH. AND/OR ELEC. PENETRATIONS
    C. CUTTING AND PATCHING FOR WORK REQUIRED BY MECH. AND/OR ELEC.
29. HOT WATER LINES AND DRAIN LINES UNDERNEATH ACCESSIBLE SINKS SHALL BE INSULATED.
30. NOT USED.
31. PROVIDE SEISMIC SPLAY WIRES & PROVIDE COMPRESSION STRUTS FOR ACOUSTICAL TILE & GYP BD SUSPENSION SYSTEMS.
32. ALL CONSTRUCTION SHALL COMPLY TO RESPECTIVE SEISMIC REQUIREMENT SEE STRUCT DRAWINGS FOR SEISMIC CHARACTERISTICS.
33. EXPOSED ENDS OF ALL PROJECTING ELEMENTS SUCH AS SILLS, LEDGES & SIMILAR COMPONENTS FABRICATED IN METAL, STONE & OTHER MATERIALS SHALL BE FINISHED SAME AS FACE.

SPECIALTIES AND EQUIPMENT

MARK	DESCRIPTION	CF	CI	OF	OI	ROOMS
	WALKWAY CANOPY (ALTERNATE)	X	X			EXTERIOR
	DOOR CANOPY	X	X			GYM, KITCHEN
ACP-1	SOUND PANELS-CEILING	X	X			GYM
AWP-1	ACOUSTICAL WALL PANELS	X	X			MUSIC ROOM
AWP-2	SOUND PANELS-WALL	X	X			GYM
D	DRYER	X	X			GYM, EC
E1	KILN	X	X			ART CLASSROOM
E2	PROJECTION SCREEN	X	X			DINING
E3	BLEACHERS	X	X			GYM
E4	DIVIDER CURTAIN (ALTERNATE)	X	X			GYM
E5	SCORE BOARD WITH SHOT CLOCK	X	X			GYM
E6	OVERHEAD POWER	X	X			MAKERSPACE
E7	STAGE LIFT	X	X			STAGE
E8	REFRIGERATOR	X	X			WORKROOM
E9	SMARTBOARD		X	X		CLASSROOM
E9	MICROWAVE			X	X	WORKROOM
E10	COPIER			X	X	ADMIN
E11	SCORE KEEPER TABLE, MOVEABLE			X	X	GYM
E12	WRESTLING MAT LIFT			X	X	GYM
E13	LARGE SCREEN TV			X	X	MEDIA CENTER
E14	PROJECTION SCREEN	X	X			GYM
E15	REFRIGERATOR			X	X	SCIENCE LABS
E16	REFRIGERATOR	X	X			SNACK BAR
E17	ICE MACHINE	X	X			SNACK BAR
F1	ADA BENCH	X	X			LOCKER ROOM
F2	BENCH	X	X			LOCKER ROOM
F3	CUBBY/LOCKER	X	X			LOCKER ROOM
F4	SAFETY GOGGLE CABINET	X	X			SCIENCE LABS
F5	OUTDOOR BENCH, NORWOOD COMMERCIAL FURNITURE, NOR-NW123SM-D8	X	X			SITE FURNISHING
F6	STAGE CURTAIN	X	X			STAGE
F7	WRESTLING MAT			X	X	GYM
F8	GREEN SCREEN, FREE-STANDING			X	X	MAKERSPACE
F9	STORAGE SHELVING			X	X	MEDIA CENTER
F10	INSTRUMENT LOCKERS			X	X	MUSIC ROOM
F11	FLAMMABLE MATERIALS CABINET			X	X	SCIENCE LABS
F12	WALL PADS	X	X			GYM
F13	LOCKERS	X	X			KITCHEN
S1	KILN DRYING RACK					ART CLASSROOM
S2	ADJUSTABLE STORAGE SHELVING	X	X			ART CLASSROOM
S3	ADJUSTABLE STORAGE SHELVING	X	X			JANITOR
TA-1	FRAMELESS MIRROR	X	X			RESTROOMS
TA-2	GRAB BAR	X	X			RESTROOMS
TA-3	TOILET PAPER DISPENSER		X	X		RESTROOMS
TA-4	PAPER TOWEL DISPENSER		X	X		RESTROOMS
TA-5	SOAP DISPENSER		X	X		RESTROOMS
TA-6	SANITARY NAPKIN DISPENSER		X	X		RESTROOMS
TA-7	SANITARY NAPKIN DISPOSAL	X	X			RESTROOMS
TA-8	WHITEBOARD	X	X			CLASSROOM
TA-9	SHOWER CURTAIN ROD	X	X			EC TOILET/SHOWER
TA-9	SHOWER CURTAIN & HOOKS			X	X	EC TOILET/SHOWER
TA-10	MOP AND BROOM HOLDER	X	X			JANITOR
TA-12	PRIVACY CURTAIN	X	X			EC TOILET/SHOWER
TA-13	ELECTRIC HAND DRYER	X	X			RESTROOMS
TA-14	TACK STRIP	X	X			ART CLASSROOM
TA-14	TACK STRIP	X	X			CORRIDOR
TA-15	ADJUSTABLE HEIGHT CHANGING TABLE	X	X			EC TOILET/SHOWER
TA-16	TOILET PARTITIONS	X	X			RESTROOMS
W	WASHER	X	X			GYM, EC

ARCHITECT

ksqdesign

NEW YORK OKLAHOMA NORTH CAROLINA
TEXAS COLORADO SOUTH CAROLINA

KSQ Design
1930 CAMDEN ROAD, SUITE 260
CHARLOTTE, NC 28203
704.364.3400 office
704.364.7080 fax
www.ksq.design

Owner
BRUNSWICK COUNTY SCHOOLS
199 SESSIONS DRIVE
BOLIVIA, NC 28422
910.253.2900 office
www.bcswan.net

Civil Engineer
McGILL ASSOCIATES
712 VILLAGE ROAD SW, SUITE 103
SHALLOTTE, NC 28470
910.755.5872 office
www.mcgillengineer.com

Structural Engineer
CRISER, TROUTMAN, TANNER
3809 PEACHTREE AVE., SUITE 102
WILMINGTON, NC 28403
910.397.2971 office
www.cttengineering.com

MEP Engineer
KSQ DESIGN
1930 CAMDEN ROAD, SUITE 260
CHARLOTTE, NC 28203
704.364.3400 office
www.ksq.design

Electrical Consultant
QUALITY CONSULTING ENGINEERS, PLLC
6277-600 CAROLINA COMMONS DRIVE,
#350 INDIAN LAND SC 29707
803.207.5450 office
djones@qualityconsultingengineers.com

Acoustic & Technology Consultant
THORBURN ASSOCIATES
401 N. TYRON STREET, 10TH FLOOR
CHARLOTTE, NC 28202
510.886.7826 office
www.TA-Inc.com

Building Envelope Consultant
SKA ENGINEERING
7741 MARKET STREET, SUITE F
WILMINGTON, NC 28411-9444
910.442.2000 office
www.skaeng.com

Food Service Consultant
HERBIN DESIGN
7325 DORN CIRCLE
CHARLOTTE, NC 28212-6914
704.900.0922
www.herbin.com

KSQ ARCHITECTS, PC — Engineers • Architectural • Interiors — 51784 — North Carolina — TULSA, OK

NORTH CAROLINA REGISTERED ARCHITECT NO. 2996 — DOUGLAS A. BURIS

BRUNSWICK COUNTY SCHOOLS — A Community of Learners

TOWN CREEK MIDDLE SCHOOL

6370 LAKE PARK DRIVE SE
WINNABOW, NC 28479

KEY PLAN



REVISIONS

No.	Description	Date
1	Addendum #1	6-7-2018
2	Addendum #2	6-19-2018

ISSUED: CONSTRUCTION DOCUMENTS

DATE: 05/24/2018

SCALE: As indicated

SHEET NAME:
GENERAL NOTES / ABBREVIATIONS / LEGENDS AND SYMBOLS

SHEET NUMBER:
G-031

ORIGINAL BY: Author
LAST MODIFIED BY:
C:\Archi\Autodesk\Documents\17000_BCS_TCMS_Arch_v17_ddouglas.rvt
6/18/2018 10:53:49 AM

COPYRIGHT © 2017 KSQ ARCHITECTS, PC