

Leland Town Hall Addition & Renovations

Addendum 3

May 10, 2024

To: All Plan Holders

From: Jenny Williams, AIA



General Items

1. Bid date and time remain unchanged.
2. See the following link for access to the building's existing drawings:
[Leland Town Hall – Existing Drawings](#).

Specification Items

1. Spec Section 04 7200 Cast Stone Masonry: Revised specification is attached.
 - a. Part 1 General, 1.04 Submittals; Add the following:
 - G. *Shop Drawings: Submit manufacturers shop drawings including profiles, cross-sections, reinforcement, exposed faces, arrangement of joints, anchoring methods, anchors, annotation of stone types and their location.*
 - b. Part 2 Products, 2.03 Materials, Item I; revise to read:
Embedded Anchors, Dowels, and Inserts: standard building stone anchors, dowels, and inserts commercially available in non-corrosive material such as galvanized steel or Type 304 stainless steel, of type and size as required for conditions.
2. Spec Section 09 6813 Tile Carpeting: Revised specification is attached.
 - a. Part 2 Products, 2.02 Materials, A. Tile Carpeting; delete Item "1. Product: Captivate & Radiance manufactured by Shaw Contract Group."
 - b. Part 2 Products, add the following:
 - 2.04 SCHEDULE
 - A. *CPT-1: All areas receiving new carpet tile, unless noted otherwise.*
 1. *Basis of Design: Captivate manufactured by Shaw Contract Group.*
 - B. *CPT-2: Conference Rooms, Council Conference, Training Council Overflow, Open Offices*
 1. *Product: Radiance manufactured by Shaw Contract Group.*
3. Spec Section 22 1316 Sanitary Waste and Vent Piping: Revised specification is attached.
 - a. Part 3 Execution, 3.10 Piping Schedule; Add the following:
 - C. *Underground, storm, soil, waste, vent and condensate piping shall be the following:*
 1. *Solid-wall PVC pipe, PVC socket fittings, and solvent-cemented joints.*
 2. *Dissimilar Pipe-Material Couplings: Unshielded, nonpressure transition couplings.*

Leland Town Hall Addition & Renovations

Addendum 3

Drawing Items

1. Sheet A6.0 Finish Schedule: Room 102A Corridor's ceiling finish has been revised to "ETR ACT".

Clarifications

1. Roller shades are to be installed at all exterior windows in the building addition except for the corridors and vestibules.
2. All notes for "weather barrier" in the construction drawings refer to the product specified in section 07 2700 Air Barriers.

Approved Substitutions

The following have been reviewed and accepted:

1. ELCW Series – Drywall Beach Application by Erie Metal Specialties, Inc. is an approved manufacturer for Interior Non-Fire-Rated Wall/Ceiling Joints Subject to Wind & Seismic Movement expansion joint cover assembly.

End of Addendum 3

**SECTION 04 7200
CAST STONE MASONRY**

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Architectural cast stone.
- B. Units required are indicated on drawings as "cast stone".
- C. Units required are:
 - 1. Exterior wall units, including sills and water tables.

1.02 RELATED REQUIREMENTS

- A. Section 04 2000 - Unit Masonry: Installation of cast stone in conjunction with masonry.
- B. Section 07 9200 - Joint Sealants: Sealing joints indicated to be left open for sealant.

1.03 REFERENCE STANDARDS

- A. ACI CODE-318 - Building Code Requirements for Structural Concrete and Commentary; 2019 (Reapproved 2022).
- B. ASTM A123/A123M - Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products; 2017.
- C. ASTM A615/A615M - Standard Specification for Deformed and Plain Carbon-Steel Bars for Concrete Reinforcement; 2020.
- D. ASTM A767/A767M - Standard Specification for Zinc-Coated (Galvanized) Steel Bars for Concrete Reinforcement; 2016.
- E. ASTM A884/A884M - Standard Specification for Epoxy-Coated Steel Wire and Welded Wire Reinforcement; 2014.
- F. ASTM A1064/A1064M - Standard Specification for Carbon-Steel Wire and Welded Wire Reinforcement, Plain and Deformed, for Concrete; 2018a.
- G. ASTM C33/C33M - Standard Specification for Concrete Aggregates; 2018.
- H. ASTM C150/C150M - Standard Specification for Portland Cement; 2020.
- I. ASTM C270 - Standard Specification for Mortar for Unit Masonry; 2019.
- J. ASTM C494/C494M - Standard Specification for Chemical Admixtures for Concrete; 2019.
- K. ASTM C1364 - Standard Specification for Architectural Cast Stone; 2023.

1.04 SUBMITTALS

- A. See Section 01 3000 - Administrative Requirements, for submittal procedures.
- B. Product Data: Test results of cast stone components made previously by the manufacturer.
- C. Mortar Color Selection Samples.
- D. Verification Samples: Pieces of actual cast stone components not less than 6 inches (152 mm) square, illustrating range of color and texture to be anticipated in components furnished for the project.
- E. Full-Size Samples, For Review:
 - 1. Basic Shapes: One of each.
 - 2. Accent, Trim and Specialty Shapes: One of each.
- F. Manufacturer's Qualification Data: Documentation showing compliance with specified requirements.
- G. Shop Drawings: Submit manufacturers shop drawings including profiles, cross-sections, reinforcement, exposed faces, arrangement of joints, anchoring methods, anchors, annotation of stone types and their location.

1.05 QUALITY ASSURANCE

- A. Manufacturer Qualifications:
 - 1. A firm with a minimum of 5 years experience producing cast stone of types required for project.
 - 2. Current producer member of the Cast Stone Institute or the Architectural Precast Association.
 - 3. Manufacturer's production facility currently holds a Plant Certification from the Cast Stone Institute or the Architectural Precast Association.
 - 4. Adequate plant capacity to furnish quality, sizes, and quantity of cast stone required without delaying progress of the work.

1.06 MOCK-UPS

- A. See mockup requirement in Section 04 2000; provide full size cast stone components for installation in mock-up of exterior wall.
- B. See Section 01 4000 - Quality Requirements for additional requirements.
- C. Remove mock-up not incorporated into the work and dispose of debris.

1.07 DELIVERY, STORAGE, AND HANDLING

- A. Deliver cast stone components secured to shipping pallets and protected from damage and discoloration. Protect corners from damage.
- B. Store cast stone components and installation materials in accordance with manufacturer's instructions.
- C. Store cast stone components on pallets with nonstaining, waterproof covers. Ventilate under covers to prevent condensation. Prevent contact with dirt.
- D. Protect cast stone components during handling and installation to prevent chipping, cracking, or other damage.
- E. Store mortar materials where contamination can be avoided.
- F. Schedule and coordinate production and delivery of cast stone components with unit masonry work to optimize on-site inventory and to avoid delaying the work.

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. Architectural Cast Stone:
 - 1. Any current producer member of the Architectural Precast Association.
 - 2. Any current producer member of the Cast Stone Institute.

2.02 ARCHITECTURAL CAST STONE

- A. Cast Stone: Architectural concrete product manufactured to simulate appearance of natural sandstone, complying with ASTM C1364.
 - 1. Compressive Strength: As specified in ASTM C1364; calculate strength of pieces to be field cut at 80 percent of uncut piece.
 - 2. Freeze-Thaw Resistance: Demonstrated by laboratory testing in accordance with ASTM C1364.
 - 3. Surface Texture: Fine grained texture, with no bugholes, air voids, or other surface blemishes visible from distance of 20 feet (6 meters).
 - 4. Color: Match existing.
 - 5. Remove cement film from exposed surfaces before packaging for shipment.
- B. Shapes: Provide shapes indicated on drawings.
 - 1. Variation from Any Dimension, Including Bow, Camber, and Twist: Maximum of plus/minus 1/8 inch (3 mm) or length divided by 360, whichever is greater, but not more than 1/4 inch (6 mm).
 - 2. Unless otherwise indicated on drawings, provide:
 - a. Wash or slope of 1:12 on exterior horizontal surfaces.

- b. Drips on projecting components, wherever possible.
 - c. Raised fillets at back of sills and at ends to be built in.
- C. Reinforcement: Provide reinforcement as required to withstand handling and structural stresses; comply with ACI CODE-318.
- 1. Pieces More than 24 inches (610 mm) in Any Dimension: Provide full length two-way reinforcement of cross-sectional area not less than 0.25 percent of unit cross-sectional area.

2.03 MATERIALS

- A. Portland Cement: ASTM C150/C150M.
 - 1. For Units: Type I, white or gray as required to match Architect 's sample.
 - 2. For Mortar: Type I or II, except Type III may be used in cold weather.
- B. Coarse Aggregate: ASTM C33/C33M, except for gradation; granite, quartz, or limestone.
- C. Fine Aggregate: ASTM C33/C33M, except for gradation; natural or manufactured sands.
- D. Admixtures: ASTM C494/C494M.
- E. Water: Potable.
- F. Reinforcing Bars: ASTM A615/A615M, Grade 40 (40,000 psi) (280 MPa), deformed bars, galvanized.
 - 1. Galvanized in accordance with ASTM A767/A767M, Class I.
- G. Steel Welded Wire Reinforcement: ASTM A1064/A1064M, galvanized or ASTM A884/A884M, epoxy coated.
- H. Embedded Anchors, Dowels, and Inserts: Standard building stone anchors, dowels, and inserts commercially available in a non-corrosive material such as galvanized steel or Type 304 stainless steel, of type and size as required for conditions.
- I. Shelf Angles and Similar Structural Items: Hot-dip galvanized steel per ASTM A123/A123M, of shapes and sizes as required for conditions.
- J. Mortar: Portland cement-lime, as specified in Section 04 0511 ; do not use masonry cement.
- K. Cleaner: General-purpose cleaner designed for removing mortar and grout stains, efflorescence, and other construction stains from new masonry surfaces without discoloring or damaging masonry surfaces; approved for intended use by cast stone manufacturer and by cleaner manufacturer for use on cast stone and adjacent masonry materials.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Examine construction to receive cast stone components. Notify Architect if construction is not acceptable.
- B. Do not begin installation until unacceptable conditions have been corrected.

3.02 INSTALLATION

- A. Install in accordance with manufacturer's instructions.
- B. Install cast stone components in conjunction with masonry, complying with requirements of Section 04 2000.
- C. Mechanically anchor cast stone units indicated; set remainder in mortar.
- D. Setting:
 - 1. Drench cast stone components with clear, running water immediately before installation.
 - 2. Set units in a full bed of mortar unless otherwise indicated.
 - 3. Fill vertical joints with mortar.
 - 4. Fill dowel holes and anchor slots completely with mortar or non-shrink grout.

3.03 TOLERANCES

- A. Joints: Make all joints 3/8 inch (9.5 mm), except as otherwise detailed.
 - 1. Rake mortar joints 3/4 inch (19 mm) for pointing.

2. Remove excess mortar from face of stone before pointing joints.
 3. Point joints with mortar in layers 3/8 inch (9.5 mm) thick and tool to a slight concave profile.
 4. Leave the following joints open for sealant:
 - a. Head joints in top courses, including copings, parapets, cornices, sills, and steps.
 - b. Joints in projecting units.
 - c. Joints between rigidly anchored units, including soffits, panels, and column covers.
 - d. Joints below lugged sills and stair treads.
 - e. Joints below ledge and relieving angles.
 - f. Joints labeled "expansion joint".
- B. Installation Tolerances:
1. Variation from Plumb: Not more than 1/8 inch in 10 feet (3 mm in 3 m) or 1/4 inch in 20 feet (6 mm in 6 m) or more.
 2. Variation from Level: Not more than 1/8 inch in 10 feet (3 mm in 3 m) or 1/4 inch in 20 feet (6 mm in 6 m), or 3/8 inch (9 mm) maximum.
 3. Variation in Joint Width: Not more than 1/8 inch in 36 inches (3 mm in 900 mm) or 1/4 of nominal joint width, whichever is less.
 4. Variation in Plane Between Adjacent Surfaces (Lipping): Not more than 1/16 inch (1.5 mm) difference between planes of adjacent units or adjacent surfaces indicated to be flush with units.

3.04 REPAIR

- A. Repair chips and other surface damage noticeable when viewed in direct daylight at 20 feet (6 m).
- B. Repair with matching touch-up material provided by the manufacturer and in accordance with manufacturer's instructions.
- C. Repair methods and results subject to Architect 's approval.

3.05 CLEANING

- A. Keep cast stone components clean as work progresses.
- B. Clean completed exposed cast stone after mortar is thoroughly set and cured.
 1. Wet surfaces with water before applying cleaner.
 2. Apply cleaner to cast stone in accordance with manufacturer's instructions.
 3. Remove cleaner promptly by rinsing thoroughly with clear water.
 4. Do not use acidic cleaners.

3.06 PROTECTION

- A. Protect completed work from damage.
- B. Clean, repair, or restore damaged or mortar-splashed work to condition of new work.

END OF SECTION 04 7200

**SECTION 09 6813
TILE CARPETING**

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Carpet tile, fully adhered.
- B. Removal of existing carpet tile.

1.02 RELATED REQUIREMENTS

- A. Section 01 7419 - Construction Waste Management and Disposal: Reclamation/Recycling of new carpet tile scrap and removed carpet tile.
- B. Section 03 3000 - Cast-in-Place Concrete: Restrictions on curing compounds for concrete slabs and floors to receive adhesive-applied flooring.
- C. Section 09 0561 - Common Work Results for Flooring Preparation: Removal of existing floor coverings, cleaning, and preparation.

1.03 REFERENCE STANDARDS

- A. ASTM D2859 - Standard Test Method for Ignition Characteristics of Finished Textile Floor Covering Materials; 2016.
- B. ASTM E648 - Standard Test Method for Critical Radiant Flux of Floor-Covering Systems Using a Radiant Heat Energy Source; 2019a, with Editorial Revision (2020).
- C. CRI 104 - Standard for Installation of Commercial Carpet; 2015.
- D. NFPA 253 - Standard Method of Test for Critical Radiant Flux of Floor Covering Systems Using a Radiant Heat Energy Source; 2019.

1.04 SUBMITTALS

- A. See Section 01 3000 - Administrative Requirements, for submittal procedures.
- B. Product Data: Provide data on specified products, describing physical and performance characteristics; sizes, patterns, colors available, and method of installation.
- C. Selection Samples: Provide physical samples of manufacturer's full range of standard colors and patterns.
- D. Verification Samples: Submit two full-size carpet tiles illustrating color and pattern design for each carpet color and pattern selected.
- E. Maintenance Data: Include maintenance procedures, recommended maintenance materials, and suggested schedule for cleaning.
- F. Maintenance Materials: Furnish the following for Owner's use in maintenance of project.
 - 1. See Section 01 6000 - Product Requirements, for additional provisions.
 - 2. Extra Carpet Tiles: Quantity equal to 5 percent of total installed of each color and pattern installed.

1.05 QUALITY ASSURANCE

- A. Manufacturer Qualifications: Company specializing in manufacturing specified carpet tile with minimum three years documented experience.

1.06 FIELD CONDITIONS

- A. Store materials in area of installation for minimum period of 24 hours prior to installation.

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. Tile Carpeting:
 - 1. Basis of Design Manufacturer: Shaw Contract Group: www.shawcontract.com/en-us
 - 2. Other Acceptable Manufacturers:
 - a. Milliken & Company: www.milliken.com/#sle.

- b. Mohawk Group: www.mohawkgroup.com/#sle.
- c. Substitutions: See Section 01 6000 - Product Requirements.

2.02 MATERIALS

- A. Tile Carpeting : Tufted, manufactured in one color dye lot.
 - 1. Tile Size: 24 by 24 inch (____by____ mm), nominal.
 - 2. Thickness: 0.236 inch (____ mm).
 - 3. Color and Pattern: To be selected from manufacturer's full range.
 - 4. Primary Backing Material: Synthetic.
 - 5. Secondary Backing Material: Ecoworx Tile.

2.03 ACCESSORIES

- A. Subfloor Filler: White premix latex; type recommended by flooring material manufacturer.
- B. Edge Strips: Rubber, color as selected by Architect.
- C. Carpet Tile Adhesive: Recommended by carpet tile manufacturer; releasable type.

2.04 SCHEDULE

- A. CPT-1: All areas receiving new carpet tile, unless noted otherwise.
 - 1. Basis of Design: Captivate manufactured by Shaw Contract Group.
- B. CPT-2: Conference Rooms, Council Conference, Training Council Overflow, Open Offices
 - 1. Basis of Design: Radiance manufactured by Shaw Contract Group.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that subfloor surfaces are smooth and flat within tolerances specified for that type of work and are ready to receive carpet tile.
- B. Verify that subfloor surfaces are dust-free and free of substances that could impair bonding of adhesive materials to subfloor surfaces.
- C. Cementitious Subfloor Surfaces: Verify that substrates are ready for flooring installation by testing for moisture and alkalinity (pH).
 - 1. Test in accordance with ASTM F710
 - 2. Obtain instructions if test results are not within limits recommended by flooring material manufacturer and adhesive materials manufacturer.
- D. Verify that required floor-mounted utilities are in correct location.

3.02 PREPARATION

- A. Prepare floor substrates for installation of flooring in accordance with Section 09 0561.

3.03 INSTALLATION

- A. Starting installation constitutes acceptance of subfloor conditions.
- B. Install carpet tile in accordance with manufacturer's instructions.
- C. Blend carpet from different cartons to ensure minimal variation in color match.
- D. Cut carpet tile clean. Fit carpet tight to intersection with vertical surfaces without gaps.
- E. Lay carpet tile in monolithic pattern, with pile direction parallel to next unit, set parallel to building lines.
- F. Locate change of color or pattern between rooms under door centerline.
- G. Fully adhere carpet tile to substrate.
- H. Trim carpet tile neatly at walls and around interruptions.
- I. Complete installation of edge strips, concealing exposed edges.

3.04 CLEANING

- A. Remove excess adhesive without damage, from floor, base, and wall surfaces.

B. Clean and vacuum carpet surfaces.

END OF SECTION 09 6813

**SECTION 22 1316
SANITARY WASTE AND VENT PIPING**

PART 1 GENERAL

1.01 SUMMARY

- A. Section Includes:
 - 1. Pipe, tube, and fittings.
 - 2. Specialty pipe fittings.

1.02 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated.

1.03 INFORMATIONAL SUBMITTALS

- A. Field quality-control reports.

1.04 QUALITY ASSURANCE

- A. Piping materials shall bear label, stamp, or other markings of specified testing agency.
- B. Comply with NSF/ANSI 14, "Plastics Piping Systems Components and Related Materials," for plastic piping components. Include marking with "NSF-dwv" for plastic drain, waste, and vent piping and "NSF-sewer" for plastic sewer piping.

PART 2 PRODUCTS

2.01 PIPING MATERIALS

- A. Comply with requirements in "Piping Schedule" Article for applications of pipe, tube, fitting materials, and joining methods for specific services, service locations, and pipe sizes.

2.02 HUB-AND-SPIGOT, CAST-IRON SOIL PIPE AND FITTINGS

- A. Pipe and Fittings: ASTM A 74, Service class.
- B. Gaskets: ASTM C 564, rubber.

2.03 HUBLESS, CAST-IRON SOIL PIPE AND FITTINGS

- A. Pipe and Fittings: ASTM A 888 or CISPI 301.
- B. CISPI, Hubless-Piping Couplings:
 - 1. Standards: ASTM C 1277 and CISPI 310.
 - 2. Description: Stainless-steel corrugated shield with stainless-steel bands and tightening devices; and ASTM C 564, rubber sleeve with integral, center pipe stop.

2.04 PVC PIPE AND FITTINGS

- A. Solid-Wall PVC Pipe: ASTM D 2665, drain, waste, and vent.

- B. PVC Socket Fittings: ASTM D 2665, made to ASTM D 3311, drain, waste, and vent patterns and to fit Schedule 40 pipe.
- C. Adhesive Primer: ASTM F 656.
- D. Solvent Cement: ASTM D 2564.

2.05 SPECIALTY PIPE FITTINGS

- A. Transition Couplings:
 - 1. General Requirements: Fitting or device for joining piping with small differences in OD's or of different materials. Include end connections same size as and compatible with pipes to be joined.
 - 2. Fitting-Type Transition Couplings: Manufactured piping coupling or specified piping system fitting.
 - 3. Unshielded, Nonpressure Transition Couplings:
 - a. Standard: ASTM C 1173.
 - b. Description: Elastomeric, sleeve-type, reducing or transition pattern. Include shear ring and corrosion-resistant-metal tension band and tightening mechanism on each end.
 - c. Sleeve Materials:
 - 1) For Cast-Iron Soil Pipes: ASTM C 564, rubber.
 - 2) For Plastic Pipes: ASTM F 477, elastomeric seal or ASTM D 5926, PVC.
 - 3) For Dissimilar Pipes: ASTM D 5926, PVC or other material compatible with pipe materials being joined.

PART 3 EXECUTION

3.01 EARTH MOVING

- A. Comply with requirements for excavating, trenching, and backfilling specified in Section 312000 "Earth Moving."

3.02 PIPING INSTALLATION

- A. Drawing plans, schematics, and diagrams indicate general location and arrangement of piping systems. Indicated locations and arrangements were used to size pipe and calculate friction loss, expansion, pump sizing, and other design considerations. Install piping as indicated unless deviations to layout are approved on coordination drawings.
- B. Install piping in concealed locations unless otherwise indicated and except in equipment rooms and service areas.
- C. Install piping indicated to be exposed and piping in equipment rooms and service areas at right angles or parallel to building walls. Diagonal runs are prohibited unless specifically indicated otherwise.
- D. Install piping above accessible ceilings to allow sufficient space for ceiling panel removal.
- E. Install piping at indicated slopes.
- F. Install piping free of sags and bends.

- G. Install fittings for changes in direction and branch connections.
- H. Make changes in direction for soil and waste drainage and vent piping using appropriate branches, bends, and long-sweep bends. Sanitary tees and short-sweep 1/4 bends may be used on vertical stacks if change in direction of flow is from horizontal to vertical. Use long-turn, double Y-branch and 1/8-bend fittings if two fixtures are installed back to back or side by side with common drain pipe. Straight tees, elbows, and crosses may be used on vent lines. Do not change direction of flow more than 90 degrees. Use proper size of standard increasers and reducers if pipes of different sizes are connected. Reducing size of drainage piping in direction of flow is prohibited.
- I. Lay buried building drainage piping beginning at low point of each system. Install true to grades and alignment indicated, with unbroken continuity of invert. Place hub ends of piping upstream. Install required gaskets according to manufacturer's written instructions for use of lubricants, cements, and other installation requirements. Maintain swab in piping and pull past each joint as completed.
- J. Install soil and waste drainage and vent piping at the following minimum slopes unless otherwise indicated:
 1. Building Sanitary Drain: 2 percent downward in direction of flow for piping NPS 3 and smaller; 1 percent downward in direction of flow for piping NPS 4 and larger.
 2. Vent Piping: 1 percent down toward vertical fixture vent or toward vent stack.
- K. Install cast-iron soil piping according to CISPI's "Cast Iron Soil Pipe and Fittings Handbook," Chapter IV, "Installation of Cast Iron Soil Pipe and Fittings."
- L. Install underground PVC piping according to ASTM D 2321.
- M. Plumbing Specialties:
 1. Install cleanouts at grade and extend to where building sanitary drains connect to building sanitary sewers in sanitary drainage gravity-flow piping. Comply with requirements for cleanouts specified in Section 221319 "Sanitary Waste Piping Specialties."
 2. Install drains in sanitary drainage gravity-flow piping. Comply with requirements for drains specified in Section 221319 "Sanitary Waste Piping Specialties."
- N. Do not enclose, cover, or put piping into operation until it is inspected and approved by authorities having jurisdiction.
- O. Install sleeves for piping penetrations of walls, ceilings, and floors.
- P. Install sleeve seals for piping penetrations of concrete walls and slabs.
- Q. Install escutcheons for piping penetrations of walls, ceilings, and floors.

3.03 JOINT CONSTRUCTION

- A. Join hub-and-spigot, cast-iron soil piping with gasket joints according to CISPI's "Cast Iron Soil Pipe and Fittings Handbook" for compression joints.
- B. Join hubless, cast-iron soil piping according to CISPI 310 and CISPI's "Cast Iron Soil Pipe and Fittings Handbook" for hubless-piping coupling joints.
- C. Plastic, Nonpressure-Piping, Solvent-Cement Joints: Clean and dry joining surfaces. Join pipe and fittings according to the following:

1. Comply with ASTM F 402 for safe-handling practice of cleaners, primers, and solvent cements.
2. PVC Piping: Join according to ASTM D 2855 and ASTM D 2665 Appendixes.

3.04 SPECIALTY PIPE FITTING INSTALLATION

A. Transition Couplings:

1. Install transition couplings at joints of piping with small differences in OD's.
2. In Drainage Piping: Unshielded and Shielded, nonpressure transition couplings.

3.05 HANGER AND SUPPORT INSTALLATION

A. Comply with requirements for pipe hanger and support devices and installation specified in Section 220529 "Hangers and Supports for Plumbing Piping and Equipment."

1. Install carbon-steel pipe hangers for horizontal piping in noncorrosive environments.
2. Install carbon-steel pipe support clamps for vertical piping in noncorrosive environments.
3. Vertical Piping: MSS Type 8 or Type 42, clamps.
4. Install individual, straight, horizontal piping runs:
 - a. 100 Feet and Less: MSS Type 1, adjustable, steel clevis hangers.
5. Base of Vertical Piping: MSS Type 52, spring hangers.

B. Support horizontal piping and tubing within 12 inches of each fitting and coupling.

C. Support vertical piping and tubing at base and at each floor.

D. Rod diameter may be reduced one size for double-rod hangers, with 3/8-inch minimum rods.

E. Install hangers for cast-iron soil piping with the following maximum horizontal spacing and minimum rod diameters:

1. NPS 1-1/2 and NPS 2: 60 inches with 3/8-inch rod.
2. NPS 3: 60 inches with 1/2-inch rod.
3. NPS 4: 60 inches with 5/8-inch rod.
4. Spacing for 10-foot lengths may be increased to 10 feet. Spacing for fittings is limited to 60 inches.

F. Install supports for vertical cast-iron soil piping every 15 feet.

G. Support piping and tubing not listed above according to MSS SP-69 and manufacturer's written instructions.

3.06 CONNECTIONS

A. Drawings indicate general arrangement of piping, fittings, and specialties.

B. Connect soil and waste piping to exterior sanitary sewerage piping. Use transition fitting to join dissimilar piping materials.

C. Connect drainage and vent piping to the following:

1. Plumbing Fixtures: Connect drainage piping in sizes indicated, but not smaller than required by plumbing code.

2. Plumbing Fixtures and Equipment: Connect atmospheric vent piping in sizes indicated, but not smaller than required by authorities having jurisdiction.
 3. Plumbing Specialties: Connect drainage and vent piping in sizes indicated, but not smaller than required by plumbing code.
 4. Install test tees (wall cleanouts) in conductors near floor and floor cleanouts with cover flush with floor.
 5. Equipment: Connect drainage piping as indicated. Provide shutoff valve if indicated and union for each connection. Use flanges instead of unions for connections NPS 2-1/2 and larger.
- D. Where installing piping adjacent to equipment, allow space for service and maintenance of equipment.
- E. Make connections according to the following unless otherwise indicated:
1. Install unions, in piping NPS 2 and smaller, adjacent to each valve and at final connection to each piece of equipment.
 2. Install flanges, in piping NPS 2-1/2 and larger, adjacent to flanged valves and at final connection to each piece of equipment.

3.07 IDENTIFICATION

- A. Identify exposed sanitary waste and vent piping. Comply with requirements for identification specified in Section 220553 "Identification for Plumbing Piping and Equipment."

3.08 FIELD QUALITY CONTROL

- A. During installation, notify authorities having jurisdiction at least 24 hours before inspection must be made. Perform tests specified below in presence of authorities having jurisdiction.
1. Roughing-in Inspection: Arrange for inspection of piping before concealing or closing-in after roughing-in and before setting fixtures.
 2. Final Inspection: Arrange for final inspection by authorities having jurisdiction to observe tests specified below and to ensure compliance with requirements.
- B. Reinspection: If authorities having jurisdiction find that piping will not pass test or inspection, make required corrections and arrange for reinspection.
- C. Reports: Prepare inspection reports and have them signed by authorities having jurisdiction.
- D. Test sanitary drainage and vent piping according to procedures of authorities having jurisdiction or, in absence of published procedures, as follows:
1. Test for leaks and defects in new piping and parts of existing piping that have been altered, extended, or repaired. If testing is performed in segments, submit separate report for each test, complete with diagram of portion of piping tested.
 2. Leave uncovered and unconcealed new, altered, extended, or replaced drainage and vent piping until it has been tested and approved. Expose work that was covered or concealed before it was tested.
 3. Roughing-in Plumbing Test Procedure: Test drainage and vent piping except outside leaders on completion of roughing-in. Close openings in piping system and fill with water to point of overflow, but not less than 10-foot head of water. From 15 minutes before inspection starts to completion of inspection, water level must not drop. Inspect joints for leaks.

4. Finished Plumbing Test Procedure: After plumbing fixtures have been set and traps filled with water, test connections and prove they are gastight and watertight. Plug vent-stack openings on roof and building drains where they leave building. Introduce air into piping system equal to pressure of 1-inch wg. Use U-tube or manometer inserted in trap of water closet to measure this pressure. Air pressure must remain constant without introducing additional air throughout period of inspection. Inspect plumbing fixture connections for gas and water leaks.
5. Repair leaks and defects with new materials and retest piping, or portion thereof, until satisfactory results are obtained.
6. Prepare reports for tests and required corrective action.

3.09 CLEANING AND PROTECTION

- A. Clean interior of piping. Remove dirt and debris as work progresses.
- B. Protect drains during remainder of construction period to avoid clogging with dirt and debris and to prevent damage from traffic and construction work.
- C. Place plugs in ends of uncompleted piping at end of day and when work stops.

3.10 PIPING SCHEDULE

- A. Aboveground, soil, waste and condensate piping NPS 4 and smaller shall be any of the following:
 1. Service class, cast-iron soil pipe and fittings; gaskets; and gasketed joints.
 2. Solid-wall PVC pipe, PVC socket fittings, and solvent-cemented joints.
- B. Aboveground, vent piping NPS 4 and smaller shall be any of the following:
 1. Service class, cast-iron soil pipe and fittings; gaskets; and gasketed joints.
 2. Solid-wall PVC pipe, PVC socket fittings, and solvent-cemented joints.
 3. Hubless, cast-iron soil pipe and fittings; CISPI hubless-piping couplings; and coupled joints.
- C. Underground, storm, soil, waste, vent and condensate piping shall be the following:
 1. Solid-wall PVC pipe, PVC socket fittings, and solvent-cemented joints.
 2. Dissimilar Pipe-Material Couplings: Unshielded, nonpressure transition couplings.

END OF SECTION